
TV BRIDGE[™] II Kits

Pre-Wired, Pre-Assembled Box Kits for Flat Screen TV Installations




Pre-wired **TV Bridge**[™] II Kits in four styles...

1



TVBRA3K 2-gang power/low voltage w/ trim plate installed



Installation is faster because we've done the advance assembly work for you! You'll get a fully assembled, recessed box, with pre-wired receptacle, device, flexible cord and cord grip.

All you need to do is cut two openings in the wall, near a power source. There's no need to cut into your framing members or run power from a panel box.

- Mounting wing screws hold the boxes secure against the wall
- Plugs and connections stay inside the recessed boxes so TV mounts flush against the wall
- No mess! wires stay hidden behind the wall
- TV Bridge[™] II kits in four styles... TVB712BK power/low voltage box (power side angled) TVBRA2K power/low voltage box TVBRA1K Single-gang power box TVBRA3K power/low voltage box at top, single gang at bottom



1 Stauffer Industrial Park Scranton, PA 18517 800/233.4717 Fax 570/562.0646 www.aifittings.com

Patent pending

TV BRIDGE[™] II Series

Pre-wired, Ready-to-use Box Kits for Existing Walls

UPPER Box installation (TVB712BK shown)



1 Cut Top hole in wall for the TV. Cut Lower hole directly below the top hole, close to an existing outlet.



2 Drop the pre-wired device box assembly and cable through the top hole, feeding it toward the bottom hole.

Trim Plate

Pre-wired device

slotted opening

TVBRA2K

2 Attach device box to trim plate with

screws provided. Secure trim plate

to wall with mounting wing screws. Install CED130 in 2-gang boxes.

Pull cables.

TVBRA1K

box assembly CED130 with cables in




3 Place box in Top hole. Feed low voltage cables for TV through opening in box.

Tighten mounting wing screws to secure box to wall.

(continue with Lower Box installation below)

Cover Plate

3 Attach cover plate to trim plate with screws provided.



Energize TV Bridge II by plugging into power source (existing outlet) or (optional) surge protector.







LOWER Box installation




Pull pre-wired device assembly through bottom hole.





1 Stauffer Industrial Park Scranton, PA 18517 800/233.4717 Fax 570/562.0646 www.aifittings.com



TVBRA2K

R -	
0.	
TVBRA3K	

Distributed by

TV BRIDGE II 0712/25M

Ľ.

©2012 Arlington Industries,